



Comment: there are a total of 63 carbon discs between all three stacks; 21 carbon discs per stack - 10 cupped, 11 flat.

Part #	Raw Mat #	Description	WD Cost	List Cost
	041-0797	Assy, Baffle Panel	\$0.00	\$0.00
	007-0209	Assy, Bracket/Spacer Mount	\$0.00	\$0.00
	009-0075	Switch (Large); DPDT	\$0.00	\$0.00
	049-0148	Assy, Digital Ammeter	\$0.00	\$0.00
	049-0149	Assy, Digital Voltmeter	\$0.00	\$0.00
	078-0176	Insulator, Lock Collar Nomex 410, 010 Thick	\$0.00	\$0.00
	021-0168	Collar, Shaft Lock .50 ID x 1.5 OD x .25 Thick	\$0.00	\$0.00
	047-1129	DC Cable, POS	\$0.00	\$0.00
	047-1130	DC Cable, NEG	\$0.00	\$0.00
	048-0030	Assy, Fan w/Bracket	\$0.00	\$0.00
	078-0160	Insulator, Fan Assy	\$0.00	\$0.00
	132-0112	PCB (Circuit Board)	\$0.00	\$0.00
	004-0035	Assy, Handle	\$0.00	\$0.00
	145-0306	Carbon Pile Assy (3 carbon stacks w/Plates)	\$0.00	\$0.00
	025-0094	Ceramic Tube (1)	\$0.00	\$0.00
	145-0108	Carbon Disc, Flat;	\$0.00	\$0.00
	145-0124	Carbon Disc, Cupped	\$0.00	\$0.00
	076-0027	Spring, Compression	\$0.00	\$0.00
	076-0028	Spring, Compression	\$0.00	\$0.00
	047-1905	Shunt, 1000 amperes, 100 millivolts	\$0.00	\$0.00
	047-1178	Housing, Shunt	\$0.00	\$0.00
	050-0160	POS Plate, Copper Plated	\$0.00	\$0.00